

APPENDIX D
GENERAL NOTES

WEST VALLEY SANITATION DISTRICT, SANTA CLARA COUNTY

GENERAL NOTES

1. All material and methods of construction for sanitary sewers must conform to the Standard Specifications of West Valley Sanitation District. Inspection of sanitary sewer work will be carried out by said District located at 100 E. Sunnyoaks Avenue, Campbell, California. Notify District office 48 hours before requiring inspection. Telephone (408) 378-2407.
2. Unless otherwise indicated on the improvement plans, sewer pipe options are vitrified clay and PVC SDR 26 (or better.)
3. 3/4" crushed aggregate (per Section 200-1.2) shall be used for pipe bedding as set forth in Section 306-1.2.1 of the 2006 Edition of the "Greenbook" (Standard Specifications for Public Works Construction).
4. A building sewer shall be constructed for each residence, minimum slope 2%. The underground contractor shall install a clean-out for each building sewer.
5. Engineer shall submit a set of cut sheets in a form approved by the District at least one working day prior to the start of construction. Approved plan revisions requiring changes in grade or alignment will require submittal of revised cut sheets before construction.
6. Underground contractor shall be appropriately licensed and comply with District's insurance coverage and performance bond requirements.
7. Prior to construction, underground contractor to obtain excavation permit from _____.
8. Contractor shall obtain inquiry identification number from USA (800) 227-2600.
9. West Valley Sanitation District, Ordinance Code Sec. 6.060, requires the installation of a back-flow protective device in the building plumbing system when the lowest floor level is below the next upstream manhole or vertical riser rim.
10. It is the Contractor's responsibility to "pothole" any utility crossings or other underground obstructions before proceeding with construction. The Contractor should coordinate with the Design Engineer to verify the elevation and alignment of any underground appurtenances. Failure to verify locations in advance may result in construction delays pending design revisions and re-submittals for approval.
11. Contractor shall exercise proper safety procedures when working in confined space in accordance with the latest CAL/OSHA provisions.
12. All sanitary sewer lines, including 4-inch building sewers, will be TV-inspected by WVSD.
13. To accommodate the TV-inspection of sewer lines 6" or larger, the contractor will air test, ball, mandrel (for plastic pipe), and flush the system. It will be the responsibility of the contractor to insure access to the manhole. In the event the TV-inspection crew arrives to find they are unable to conduct the TV-inspections because of buried manholes, equipment or materials in the way, etc., then the developer or contractor will be charged for the time spent by WVSD.

Approved As To Design Only, Based On Information Submitted Hereon.

Robert R. Reid, RCE 47754 License Expires: December 31, 20
District Manager and Engineer

Date _____, 20__